



EROSION CONTROL NOTES:

1. Erosion control structures shall be installed per the sequencing indicated in the SWPPP and following article in this appendix.
2. Stodple stakes shall be placed as needed to direct runoff around construction areas as project progresses.
3. General location of all fences shown on this plan. All fences shall be placed along contour as needed throughout construction to protect resource destination.
4. All silt fence signs to daylight shall remain upright until protection per the detail in this appendix.
5. All catch basins installed shall have drop inlet protection installed per details in this appendix.

| NO. | DATE | REVISIONS | BY | DATE |
|-----|----------|-----------|--------|------|
| 1 | 03/10/11 | | | |
| | | Sheet | 1 of 1 | |

| |
|---|
| PHASE PLAN |
| CAMP OHR SHALOM Todd Road Town of Fallsburg County of Sullivan State of New York |
| JEFFREY PEARL 1046 E 14th Street Brooklyn, NY 11230 (718) 338-1426 |
| BERGER ENGINEERING AND SURVEYING 100 HILTON AVE. POUGHKEEPSIE N.Y. 12603 (845) 471-7383 bergerengineeringllc.com |